Notice.

The attention of the public is invited to the notification published in the Gazette No. 38, dated the 21st September 1916, calling for tenders for constructing a bridge across the Markundya stream at 3/1 mile of the Budikota Railway Feeder road.

V. AIYASWAMI IYER,
Executive Engineer.

Notice dated 18th September 1916.

Notice is hereby given that sealed tenders will be received at the office of the Sub-Division, Chikballapur, Kolar District, up to 5 P.M. of 28th October 1916, for improving the Prakarams of Sri Bhoga Nandiswaraswami temple at Nandi, Chikballapur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1917.

2. The plans, detailed estimate and conditions may be seen at the office of the Sub-Division, Chikballapur, between the hours 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Sub-Division Officer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 300 (rupees three hundred only) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for improving the Prakarams of Sri Bhoga Nandiswaraswami temple at Nandi, Chikballapur", in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Sub-Division Officer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tenders, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Sub-Division Officer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

No.	Items of work	Per	Quantity
1	Earthwork excavating, foundation and filling in	C. yd.	162
2	Burnt stone in mud	C. ft.	4,364
3	Burnt brick in mud	,,	19,797
4	Chunam plastering	Sq.	219·67
5	Mud plastering	,,	223·29
6	Honnewood battened door with hinges, bolts and iron clamps, etc. ...	S. ft.	702
7	Honnewood battened windows with hinges, bolts, hooks, iron clamps and iron bars, etc.	,,	850
8	Chocolate painting (2 coats)	Sq.	21·04
9	Burnt stone slabs, dressed, including lifting	S. ft.	1,098
10	Cut stone work	C. ft.	240
11	Concrete in chunam with plastering to the roof of ankanams	Sq.	43·24
12	Unforeseen items including constructing one drain, removing ant hills and dismantling old walls, etc.	Lump	sum.
13	Gravelling the floor with consolidation and cow dung wash, including one mile lead for gravel.	Sq.	135·67
14	Overhauling the dilapidated ankanams—		
	(*a*) Removing and relaying stone work.	C. ft.	634
	(*b*) Removing the existing concrete above the roof	Sq.	3·24
	(*c*) Putting fresh chunam concrete with plastering over the roof ...	,,	3·24
15	Bringing displaced pillar beams to normal position	Lump	sum.
16	White and colourwashing	Sq.	442·86

M. G. KRISHNASWAMI RAO,
Sub-Division Officer, Chikballapur.

TUMKUR DIVISION.

Abstract Notification.

The attention of the public is invited to the notification published in the *Mysore Gazette* dated 14th September 1916, pages 680 and 683 calling for tenders for building works and tank works in Tumkur District. The last date of tender is 30th September 1916.

C. KRISHNA IYENGAR,
Executive Engineer.